

VIEW SOLICITATION

General Information

Award Info: W912DR-08-C-0053, dated 25 September 2008, Grunley Construction Company Inc, ATTN: Kevin R. Mitchell, 15020 Shady Grove Road, Rockville, Maryland 20850, in the amount of \$2,383,000.

Solicitation Number: W912DR-08-R-0036

Restrictions: Restricted 8(a) Competitive

Title: Early Site Utilities Package for USAMRIID Replacement Project

Location: Fort Detrick, Maryland

Issue Date: 5 August 2008

Closing Date: ~~25 August 2008, 1400 hrs~~ **REV per Amd 01, 5 Sep 08, 1400 hrs, EST**

Price Range: \$5,000,000.00 - \$10,000,000.00

Period of Performance: 180 Calendar Days

NAICS: 236220

FSC: Y216

Size Standard: \$31 Million

Contracting POC: Carol Williams, 410-962-2197, email: Carol.A.Williams@usace.army.mil

Technical POC: Gary Poling, 301-619-9643

Synopsis: This proposed procurement is 8(a) competitive, NAICS 236220 size standard of \$31 Million. Estimated cost of services is between \$5,000,000.00 - \$10,000,000.00

The USAMRIID Early Site Utility package project consists of Demolition, removal and relocation of existing utilities in the footprint of the future USAMRIID Replacement Facility project. This is being done to provide a free and clear worksite for the Stage I work when the main contract is awarded.

The demolition consists of the removal of approximately 360 lf of gas line, 700 lf of sanitary sewer, 360 lf of communication cable, duct bank and manholes, 960 lf of overhead electrical power lines, and associated de-energizing and disconnection and removal of high voltage wires and electric poles.

The proposed utilities work is to consist of a new water main, information technology duct bank and an electrical power service duct bank, approximately 490 lf of 12" ductile iron pipe water main with associated thrust blocks, the addition of one (1) fire hydrant, approximately 3,023 lf of new communication duct bank and manholes, 840 lf of new electrical duct bank with associated manhole, and approximately 1,520 lf of 12" PVC sewer pipe with approximately 5 manholes, ranging from 6 to 18 feet deep.

Trenching for the new utilities in existing roadways and parking areas will require pavement replacement.

Additional information in accordance with the statement of work is included

in the request for quotations bid package. All responsible sources may submit a bid which shall be considered by the agency.

All questions shall be submitted via e-mail to Donna Leketa, Donna.Leketa@usace.army.mil. Bids can be submitted via mail to U.S. Army Corps of Engineers, Contracting Division, Room 7000, 10 South Howard Street, Baltimore, MD 21201-2530.

Site Visit: An organized site visit has been scheduled for Thursday, 14 August 2008, at 1000 hours.

Participants will meet at:

U.S. Army Corps of Engineers
Fort Detrick Integrated Program Office
1557 Porter Street. Bldg 1557
Fort Detrick, MD 21702

Plans & Specs: [Available thru Federal Business Opportunities System](#)

The solicitation will be provided in an electronic format, free of charge, to all authenticated account holders of [Federal Business Opportunities \(FBO\) System](#). To familiarize vendors with the newly released FBO system, please download the [Vendor Guide found here](#). Please note that all Corps of Engineers acquisitions are considered **Sensitive, But Unclassified Documents**, and require users to have a valid MPIN entered in the FBO system to access package.

The media through which the Government chooses to issue this solicitation will be the Internet only. This solicitation will not be issued in paper. No phone or fax request for copy of solicitation will be accepted.

Amendments: Amendment 1, dated 8 August 2008
Amendment 2, dated 20 August 2008
Amendment 3, dated 21 August 2008

Register as an Interested Party: [Download the attached form](#), complete, and return as directed.