

# DEACTIVATED NUCLEAR POWER PLANT PROGRAM SM-1, FT BELVOIR, VA

WM2018

Session 097b US Army Corps of Engineers - Deactivated NPP Program D&D Contracting Opportunities

Brenda Barber, P.E.

Hans Honerlah, CHMM

Baltimore District, CENAB-ENE

March 2018

*"The views, opinions and findings contained in this report are those of the authors(s) and should not be construed as an official Department of the Army position, policy or decision, unless so designated by other official documentation."*



US Army Corps  
of Engineers®



# TOPICS

- History
- Decommissioning Planning



US Army Corps  
of Engineers®



U.S. ARMY

## SM-1 TIMELINE: DETAILS


- SM-1 Reactor Startup: April 1957
  - Core II installed, June 1961
  - Core III installed, July 1968
- Last operation: March 1973
- Minimal Decommissioning: 1973 – November 1974
- USACHPPM Survey: October 1996
- Contractor Gamma Surveys: 1997 and 2009
- Core Component Activation Analysis: 2003
- Contractor Historical Site Assessment: 2003
- Contractor Characterization Survey Report: 2013
- Contractor Dap Gap Analysis: 2015
- Archeological Survey: 2016
- Supplemental Field Characterization: 2016



US Army Corps  
of Engineers®



U.S. ARMY



## 1956 Construction Photos



US Army Corps  
of Engineers®



# PRE-SHUTDOWN DECOMMISSIONING ACTIVITIES

- Cleaned out Diesel Building
- Cleaned up Retention Building and Waste Facility
- Cleaned up “Hot Maintenance Area”
- Cleaned up secondary system
- Dug up old piping not in use
  - including discharge from retention sump (seal pit)
- Dug up selected “hot dirt areas”



US Army Corps  
of Engineers®



# POST-SHUTDOWN DECOMMISSIONING ACTIVITIES

- Laid up systems; generally drained of oil and filled with preservative or air dried
- Shipped absorbers, fuel, and neutron sources
- Drained and flushed primary systems, including spent fuel pit
- Cut and welded penetrations to Vapor Container
- Removed contaminated piping outside of the Vapor Container (VC), including decontamination of vent and blowdown systems
- Peeled out liner, decontaminated, welded shut spent chute, installed cover on Spent fuel pit



US Army Corps  
of Engineers®



# POST-SHUTDOWN DECOMMISSIONING ACTIVITIES

- Conducted final survey of Gunston Cove
- Cleaned and sealed VC door with chain lock system
- Filled pipe pit with concrete
- Removed Waste Facility tanks, building, and pad
- Removed Retention Building
- Removed contaminated underground piping
- Secured and posted restricted areas: Modification (MOD) area, VC, primary make-up tank room, spent fuel pit area, demineralizer room, fan loft
- Demolished Guard House (Building 373)
- Demolished Flammable Storage Building (Building 376)
- Demolished Tree House Mockup (Building A390)
- Decontaminated underground liquid radioactive waste tanks outside Training Building (Building 358) and filled them with concrete



US Army Corps  
of Engineers®



# PRIOR CHARACTERIZATION EFFORTS TO SUPPORT DECOMMISSIONING PLANNING

- Gamma walkover surveys inside the fenced area
  - Completed in 2009; small area surveyed in 2016
- Biased and systematic soil sampling
  - Executed in 2010 and 2016
- In-plant survey to determine H-3 and alpha isotopic activity
  - Considered complete outside the VC
  - Additional samples for HTD isotopes (including H-3) collected in 2016
  - Alpha false-positive/radon analysis conducted in 2016
- Scoping surveys of buildings/sites associated with SM-1
  - Completed in 2010



US Army Corps  
of Engineers®





# PRIOR CHARACTERIZATION EFFORTS TO SUPPORT DECOMMISSIONING PLANNING

- More extensive survey of Gunston Cove sediment
  - Completed in 2010 (20 samples collected between Whitestone Pt. and discharge pipe)
- Sampling of underground pipes
  - All pipe waste and outfall pipes assumed to be contaminated
  - Geophysical surveys to verify pipes present in 2010 and 2016
  - Investigation of sewer pipes still to be planned/executed
- Soil under SM-1 to be sampled
  - Soil is assumed to be impacted and require disposal as LLRW
  - Sampling not considered to have a significant impact on cost estimates or planning efforts



US Army Corps  
of Engineers®



# DECOMMISSIONING PLANNING EFFORTS

- Decommissioning Planning is underway – anticipate completion by 2019
  - Contract was awarded in 2014
  - Scope includes:
    - review historical documents associated with the All Hazards Analysis
    - prepare planning documents that will support the Army Reactor Office issuing the USACE a decommissioning permit for the SM-1 reactor
    - comply with other relevant Federal and State requirements that will support the long term decommissioning planning
    - Ensure adherence of project activities to NRC, Army, and Federal standards and guidance , as well as, other Federal standards and guidance where relevant, and
    - coordinate with appropriate federal, state, and public parties to support issuance of decommissioning permit and other NEPA requirements.



US Army Corps  
of Engineers®



# MAJOR DECOMMISSIONING PLANNING DOCUMENTS

- Final Disposal Plan, Schedule and Cost Estimate
- Waste Management Plan
- Environmental Assessment
- Section 106 Effects Assessment and agreement document
- Decommissioning Plan



US Army Corps  
of Engineers®



# DECOMMISSIONING CHALLENGES

- Site has a small footprint and limited area for infrastructure
- Limited transportation routes off installation
- Coordination with the installation staff
- Proximity to base housing
- Proximity to the U.S. Capital



US Army Corps  
of Engineers®



# Questions?



US Army Corps  
of Engineers®



U.S. ARMY