TABLE OF CONTENTS

Page

EXECUTIVE SUMMARY ES-1

LIST OF APPENDICES viii

LIST OF FIGURES ix

LIST OF TABLES xi

LIST OF ABBREVIATIONS, ACRONYMS, AND UNITS xiv

GLOSSARY OF TECHNICAL TERMS GL-1

INDEX OF SECTIONS IN-1

1. **INTRODUCTION** 1-1

1.1 **BACKGROUND** 1-1
1.2 **PROJECT PURPOSE AND NEED** 1-5
1.2.1 Purpose 1-5
1.2.2 Need and Problem Identification 1-5
1.2.2.1 Economic Support for Harbor Dredging 1-5
1.2.2.2 Harbor Dredging Need 1-6
1.2.2.3 Existing Placement Sites 1-8
1.2.2.4 Applicable Federal Navigation Projects 1-9
1.3 **NEPA PROCESS** 1-12
1.4 **PROPOSED ACTION TO ACCOMMODATE HARBOR NEEDS** 1-13
1.4.1 New Placement Options 1-16
1.4.2 No Action Alternative 1-16
1.5 **PERMIT PROCESS** 1-18
1.6 **STUDY AREA** 1-19
1.7 **STUDIES COMPLETED** 1-17
1.7.1 Environmental Studies 1-21
1.7.2 Geotechnical Studies 1-21
1.7.3 Coastal Engineering Studies 1-21
1.7.4 Dredging Engineering Studies 1-21
1.7.5 Consultations and Stakeholder Involvement 1-22
1.7.6 Innovative Reuse Planning 1-23

2. **EXISTING CONDITIONS** 2-1

2.1 **ENVIRONMENTAL RESOURCES** 2-4

TABLE OF CONTENTS (continued)

Page

2.1.1 Project Setting 2-4
2.1.1.1 Location 2-4
2.1.1.2 Climate 2-4
2.1.2 Physiography and Geology 2-4
2.1.2.1 Physiography 2-4
2.1.2.1 Geology 2-6
2.1.2.2 Soils 2-7
2.1.2.3 Groundwater 2-6
2.1.3 Hydrology and Hydrodynamics 2-11
2.1.3.1 Bathymetry 2-11
2.1.3.2 Freshwater Inflow 2-13
2.1.3.3 Water Levels 2-15
2.1.3.4 Wind Conditions 2-17
2.1.3.5 Wave Conditions 2-20
2.1.3.6 Tidal Currents 2-22
2.1.4 Water Quality 2-29
2.1.4.1 Water Quality Parameters 2-29
2.1.4.2 Nutrient Sampling 2-33
2.1.5 Sediment Quality 2-35
2.1.5.1 Surface Sediment Sampling 2-36
2.1.5.2 Subsurface Sediment Sampling 2-49
2.1.5.3 Comparison of Surficial and Subsurface Chemistry Results 2-52
2.1.6 Aquatic Resources 2-52
2.1.6.1 Plankton 2-52
2.1.6.2 Fisheries 2-58
2.1.6.3 Commercial Fisheries 2-61
2.1.6.4 Essential Fish Habitat (EFH) 2-64
2.1.6.5 Benthic Community 2-65
2.1.6.6 Submerged Aquatic Vegetation (SAV) 2-70
2.1.6.7 Shallow Water Habitat (SWH) 2-72
2.1.7 Terrestrial Resources 2-74
2.1.7.1 Birds 2-74
2.1.7.2 Mammals 2-76
2.1.7.3 Reptiles and Amphibians 2-76
2.1.7.4 Wetland and Upland Habitats 2-77
2.1.8 Rare, Threatened, and Endangered (RTE) Species 2-79
2.1.9 Air Quality 2-82
2.1.10 Hazardous, Toxic, Radioactive Wastes (HTRW) 2-83
2.1.10.1 Kurt Iron and Metal (KIM) Site 2-83
2.1.10.2 Masonville Cove Sites 2-84
2.1.10.3 Munitions of Explosive Concern (MEC) 2-88
2.1.11 Navigation 2-88
2.1.12 Floodplains 2-88
2.1.13 Critical Areas 2-91
2.1.14 Coastal Zone Management 2-93

TABLE OF CONTENTS (continued)

Page

2.1.15 Wild and Scenic Rivers 2-93
2.1.16 Prime and Unique Farmland 2-93
2.2 **CULTURAL RESOURCES** 2-94
2.2.1 Historic Background-Colonial Era Occupation of Masonville Study Area 2-94
2.2.2 Historic Background-Modern Era of Occupation of Masonville Study Area 2-95
2.2.3 Previous Investigations 2-96
2.2.4 Phase I Survey Results for the Study Area 2-96
2.3 **SOCIOECONOMIC CONDITIONS** 2-100
2.3.1 Land and Water Use 2-100
2.3.1.1 Local and Regional Land Use 2-100
2.3.1.2 Water Use 2-103
2.3.2 Demographics 2-103
2.3.2.1 Population Characteristics 2-103
2.3.2.2 Housing and Income Characteristics 2-106
2.3.3 Employment and Industry 2-106
2.3.4 Environmental Justice 2-109
2.3.5 Safety to Children 2-109
2.4 **AESTHETICS AND RECREATION** 2-109
2.4.1 Aesthetics 2-110
2.4.1.1 Noise 2-110
2.4.1.2 Light 2-111
2.4.2 Recreation 2-112
2.4.2.1 Recreational Fishing and Boating 2-112
2.4.2.2 Other Recreational Activities 2-113
2.5 **MOST PROBABLE FUTURE WITHOUT PROJECT** 2-113

3. **ALTERNATIVES DEVELOPMENT AND ANALYSIS** 3-1

3.1 **PROJECT PURPOSE** 3-1
3.2 **DMMP PLANNING OBJECTIVES AND CONSTRAINTS** 3-2
3.2.1 Studies Conducted 3-2
3.2.2 Objectives and Constraints 3-3
3.2.2.1 Community Enhancements and Socioeconomic Objectives and Constraints 3-3
3.2.2.2 Environmental Objectives and Constraints 3-4
3.2.2.3 Engineering Objectives and Constraints 3-4
3.2.2.4 Economic Objectives and Constraints 3-4
3.3 **INVENTORY AND FORECAST** 3-5
3.4 **DEVELOPMENT AND SCREENING OF ALTERNATIVES** 3-5
3.4.1 Option Screening Process and History 3-5
3.4.2 State Screening Process and Dredged Material Management Program 3-6
3.4.2.1 Maryland State Screening History, 1970 – Present 3-8
3.4.2.2 Innovative Uses 3-20
3.4.2.2 Upland Options 3-22
3.4.3 Federal Dredged Material Management Plan 3-23
3.4.3.1 Federal DMMP Study Summary 3-21

TABLE OF CONTENTS (continued)

Page

3.4.3.2 Assessment of Existing Dredged Material Placement Capacity 3-26
3.4.3.3 Screening Process for the Federal DMMP 3-27
3.4.4 Differences Between the Federal and State DMMP 3-29
3.4.5 Harbor Team's Site Specific Recommendations 3-30
3.4.5.1 Masonville 3-30
3.4.5.2 BP-Fairfield 3-30
3.4.5.3 Sparrows Point 3-30
3.5 **EFFECTS AND COMPARISON OF ALTERNATIVES** 3-31
3.5.1 Environmental Evaluation Criteria 3-31
3.5.2 Evaluation Based on Environmental Criteria 3-33
3.5.3 Socioeconomic and Cultural Comparison 3-40
3.5.4 Engineering Comparison 3-40
3.5.5 Other Factors 3-40
3.5.6 Conclusions of Inter-Site Comparison 3-40
3.6 **OPPORTUNITIES ASSOCIATED WITH THE MASONVILLE DMCF** 3-41
3.7 **MASONVILLE ALTERNATIVES ANALYSIS** 3-41
3.7.1 Alignment History 3-42
3.7.1.1 Conceptual Alignments (CA) 3-43
3.7.1.2 Reconnaissance Alignment (RA) 3-45
3.7.1.3 Pre-Feasibility Alignments (PFA) 3-45
3.7.1.4 Final Feasibility Alignments (FFA) 3-47
3.7.2 Development of MPA's Masonville Feasibility Study Alternatives 3-47
3.7.2.1 Type of Containment Structure 3-48
3.7.2.2 Containment Structure Elevations 3-48
3.7.2.3 Incremental Dike Construction Plan 3-49
3.7.2.4 Borrow Source 3-49
3.7.2.5 Overburden Removal 3-50
3.7.3 Masonville Alternatives 3-52
3.7.3.1 Borrow Material and Overburden Dredging Scenarios 3-52
3.7.3.2 Study Alternatives 3-55
3.7.4 Site Design 3-57
3.7.4.1 Design Considerations and Site Layout 3-57
3.7.4.2 Typical Containment Structure Cross-Sections 3-60
3.7.5 Site Design Characteristics 3-63
3.7.5.1 Site Area 3-66
3.7.5.2 Site Capacity, Annual Placement Capacity, and Average Annual Site Usage 3-66
3.7.5.3 Site Life 3-66
3.7.5.4 Containment Structure Elevation 3-66
3.7.5.5 Final Surface Elevation 3-66
3.7.5.6 Construction Completion Date 3-67
3.7.5.7 Containment Structure Baseline Length 3-67
3.7.6 Comparison and Evaluation of Masonville Alternatives 3-67
3.7.6.1 Borrow Source and Overburden Placement Scenario Evaluation ... 3-67
3.7.6.2 Comparison of Alternatives 3-68

TABLE OF CONTENTS (continued)

Page

3.8 PREFERRED ALTERNATIVE 3-69
3.9 NO ACTION ALTERNATIVE 3-70

4. RECOMMENDED PLAN & EVALUATION 4-1

4.1 INTRODUCTION 4-1
4.2 OVERVIEW OF RECOMMENDED PLAN 4-1
4.2.1 Affected Area 4-2
4.2.2 General Site Characteristics 4-3
4.2.2.1 Dredged Material Placement Capacity and Annual Placement Capacity and Site Usage 4-3
4.2.2.2 Site Area 4-3
4.2.2.3 Site Life 4-4
4.2.3 Mitigation 4-4
4.2.4 Schedule 4-4
4.2.5 Project Cost 4-4
4.3 EXISTING CONDITIONS AND DESIGN CRITERIA 4-5
4.3.1 Hydrodynamics 4-5
4.3.2 Geotechnical Conditions 4-5
4.3.2.1 Borings 4-5
4.3.2.2 Probes 4-5
4.3.2.3 Vane Shear Testing 4-11
4.4 SITE DESIGN 4-11
4.4.1 Containment Structure and Wet Basin Retention Structure 4-12
4.4.1.1 Cofferdam (Berth Area) 4-13
4.4.1.2 Armored Containment Dike 4-13
4.4.1.3 Beach Containment Dike 4-14
4.4.1.4 Onshore Dike 4-15
4.4.1.5 Wet Basin Rock Dike 4-15
4.4.1.6 Design Quantities 4-16
4.4.2 Borrow Area 4-16
4.4.2.1 Geotechnically Suitable Construction Materials 4-17
4.4.2.2 Available Borrow 4-17
4.5 DMCF CONSTRUCTION 4-20
4.5.1 Preparatory Phase 4-20
4.5.1.1 Relocation/Demolition of Existing Infrastructure 4-20
4.5.1.2 Predredging (Removal of Overburden) 4-26
4.5.2 Containment Structure Construction 4-26
4.5.2.1 General Construction Sequence 4-27
4.5.2.2 Cofferdam 4-27
4.5.2.3 Armored Sand Dike 4-27
4.5.2.4 Beach Sand Dike 4-28
4.5.2.5 Onshore Dike 4-28
4.5.2.6 Ancillary Items 4-28
4.5.3 Wet Basin Rock Dike Construction 4-28

TABLE OF CONTENTS (continued)

Page

4.6 SITE OPERATIONS AND MAINTENANCE 4-29
4.7 SITE CLOSURE 4-29
4.8 REAL ESTATE 4-29
4.90 ADDITIONAL ENVIRONMENTAL BENEFITS 4-29
4.9.1 Sediment and Containment Encapsulation 4-29
4.9.2 Derelict Vessel Removal and Remediation 4-20
4.10 TOTAL PROJECT COST 4-30

5. IMPACTS 5-1

5.1 ENVIRONMENTAL IMPACTS 5-3
5.1.1 Physiography, Geology, Soils, and Groundwater 5-6
5.1.1.1 Physiography 5-6
5.1.1.2 Geology 5-7
5.1.1.3 Soils 5-7
5.1.1.4 Groundwater 5-8
5.1.2 Hydrology and Hydrodynamics 5-11
5.1.2.1 Hydrodynamics 5-12
5.1.2.2 Sedimentation Impacts 5-24
5.1.3 Water Quality 5-26
5.1.4 Sediment Quality 5-41
5.1.5 Aquatic Resources 5-43
5.1.5.1 Plankton 5-44
5.1.5.2 Fisheries 5-46
5.1.5.3 Commercial Fisheries 5-48
5.1.5.4 Essential Fish Habitat (EFH) 5-49
5.1.5.5 Benthic Community 5-51
5.1.5.6 Submerged Aquatic Vegetation (SAV) 5-52
5.1.5.7 Shallow Water Habitat (SWH) 5-53
5.1.6 Terrestrial Resources 5-53
5.1.6.1 Bird and Mammal Usage 5-53
5.1.6.2 Reptiles and Amphibians 5-54
5.1.6.3 Wetland and Upland Habitats 5-55
5.1.7 Rare, Threatened, and Endangered (RTE) Species 5-56
5.1.8 Air Quality 5-57
5.1.9 Hazardous, Toxic, Radioactive Wastes (HTRW) 5-59
5.1.9.1 Kurt Iron and Metal Site 5-59
5.1.9.2 Masonville Cove 5-60
5.1.9.3 Munitions of Explosive Concern (MEC) 5-61
5.1.10 Navigation 5-61
5.1.11 Floodplains 5-62
5.1.12 Critical Areas 5-62
5.1.13 Coastal Zone Management 5-63
5.1.14 Coastal Barriers 5-63
5.1.15 Wild and Scenic Rivers 5-63

TABLE OF CONTENTS (continued)

Page

5.1.16 Prime and Unique Farmland 5-63
5.2 **CULTURAL RESOURCES** 5-64
5.3 **SOCIOECONOMIC IMPACTS** 5-65
5.3.1 Land and Water Use 5-65
5.3.2 Fishery-related Economic Impacts 5-65
5.3.3 Employment and Industry 5-66
5.3.4 Environmental Justice 5-70
5.3.5 Safety to Children 5-71
5.4 **AESTHETICS AND RECREATION** 5-73
5.4.1 Aesthetics, Noise, and Light 5-73
5.4.1.1 Aesthetics 5-73
5.4.1.2 Noise 5-80
5.4.1.3 Light 5-83
5.4.2 Recreation 5-84
5.4.2.1 Recreational Boating 5-84
5.4.2.2 Recreational Fishing 5-84
5.4.2.3 Wildlife Viewing 5-85
5.4.2.4 Other Uses 5-85
5.5 **ENVIRONMENTAL BENEFITS** 5-85
5.6 **IRRETRIEVABLE USES OF RESOURCES** 5-86
5.7 **SUMMARY OF IMPACTS** 5-87
5.8 **CUMULATIVE IMPACTS** 5-92
5.8.1 Definition 5-92
5.8.2 Sources of Cumulative Impacts 5-92
5.8.3 Duration of Impacts 5-95
5.8.4 Cumulative Environmental Impacts 5-95
5.8.4.1 Physiography, Soils, and Groundwater 5-95
5.8.4.2 Hydrology and Hydrodynamics 5-98
5.8.4.3 Water Quality 5-99
5.8.4.4 Sediment Quality 5-100
5.8.4.5 Aquatic Resources 5-101
5.8.4.6 Terrestrial Resources 5-103
5.8.4.7 Rare, Threatened, and Endangered Species 5-104
5.8.4.8 Air Quality 5-105
5.8.4.9 Hazardous, Toxic, and Radioactive Wastes 5-106
5.8.4.10 Navigation 5-106
5.8.4.11 Floodplains 5-107
5.8.4.12 Critical Areas 5-107
5.8.4.13 Coastal Zone Management 5-107
5.8.4.14 Coastal Barriers 5-107
5.8.4.15 Wild and Scenic Rivers 5-107
5.8.4.16 Prime and Unique Farmland 5-108
5.8.5 Cumulative Impacts to Cultural Resources 5-108
5.8.6 Cumulative Impacts to Socioeconomic Resources 5-108
5.8.6.1 Future Land and Water Use 5-108

TABLE OF CONTENTS (continued)

Page

5.8.6.2 Fishery-related Economic Impacts 5-108
5.8.6.3 Employment and Industry 5-109
5.8.6.4 Environmental Justice 5-110
5.8.6.5 Safety to Children 5-110
5.8.7 Cumulative Impacts to Aesthetics and Recreation 5-111
5.8.7.1 Aesthetics, Noise, and Light 5-111
5.8.7.2 Recreation 5-112

6. **PROPOSED MITIGATION** 6-1

6.1 **DEVELOPMENT OF THE MITIGATION PLAN** 6-1
6.1.1 Harbor Team –Initial Suggestions 6-1
6.1.2 Continuing Outreach 6-2
6.2 **CONCEPTUAL MITIGATION PLAN** 6-2
6.2.1 Sites 6-2
6.2.1.1 Masonville Cove 6-3
6.2..2 Off-site Mitigation Projects 6-13
6.2.2 Impacts 6-16
6.2.2.1 Proposed Masonville DMCF 6-16
6.2.2.2 No Action Alternative 6-20
6.3 **MITIGATION MONITORING** 6-20

7. **IMPLEMENTATION OF RECOMMENDED PLAN** 7-1

7.1 **IMPLEMENTATION PROCESS** 7-1
7.1.1 Engineering 7-2
7.1.2 Permitting and Coordination 7-2
7.1.3 Procurement, Bidding, and Award 7-3
7.1.4 Construction 7-3
7.2 **IMPLEMENTATION SCHEDULE** 7-3
7.2.1 Site Preparation Activities 7-3
7.2.1.1 Pre-dredging 7-3
7.2.1.2 Phase I, Baltimore City Storm Drain Relocation 7-3
7.2.1.3 Phase II, Baltimore City Storm Drain Relocation and MMT Phase 2/KIM Stormwater Outfall Relocation 7-4
7.2.1.4 Remediation and Relocation of Derelict Vessels 7-4
7.2.1.5 Demolition of Piers 1, 2, and 3 7-5
7.2.1.6 Relocation of Baltimore City Waterline 7-5
7.2.2 Masonville DMCF 7-5
7.2.3 Integrated Compensatory Mitigation Projects 7-8
7.3 **KIM DERELICT VESSEL MANAGEMENT** 7-8
7.4 **MINIMIZATION OF IMPACTS** 7-9
7.5 **CONCEPTUAL TURBIDITY MONITORING PLAN** 7-10
7.6 **IMPLEMENTATION ISSUES** 7-11
7.7 **SUMMARY OF RESPONSIBILITIES** 7-11

TABLE OF CONTENTS (continued)

Page

7.4.1 Project Funding 7-11
7.4.2 Project Ownership 7-11

8. **ENVIRONMENTAL COMPLIANCE** 8-1

8.1 **REQUIREMENTS** 8-1
8.2 **PERMITTING** 8-4
8.3 **MONITORING** 8-9

9. **PUBLIC INVOLVEMENT** 9-1

9.1 **PUBLIC PARTICIPANTS** 9-2
9.1.1 General Groups 9-2
9.1.1.1 Agency Representatives 9-2
9.1.1.2 Local Government 9-2
9.1.1.3 Defined Groups 9-2
9.1.1.4 Educational Institutions 9-2
9.1.1.5 Private Citizens 9-3
9.1.2 Involved Project Groups 9-3
9.2 **COMMUNITY AND AGENCY INVOLVEMENT** 9-5
9.2.1 Issue Identification and Project Scoping 9-6
9.2.2 Coordination with the Joint Evaluation Committee 9-7
9.2.3 Agency Coordination 9-7
9.2.3.1 Federal Agencies and National Organizations 9-7
9.2.3.2 State Agencies and Organizations 9-8
9.2.3.2 Local Agencies and Organizations 9-9
9.2.4 Other Coordination and Agency Responses 9-10
9.2.4.1 Brooklyn-Curtis Bay Coalition (BCBC) 9-10
9.2.4.2 Maryland Department of Natural Resources (DNR) 9-10
9.2.4.3 Maryland Department of the Environment (MDE) 9-11
9.2.4.4 National Marine Fisheries Service (NMFS) 9-11
9.2.4.5 U.S. Fish and Wildlife Service (USFWS) 9-11
9.2.4.6 Baltimore City Department of Planning 9-11
9.2.4.7 National Park Service (NPS) 9-12
9.2.4.8 Patapsco Riverkeeper 9-12
9.2.4.9 Chesapeake Bay Foundation 9-12
9.2.4.10 Community of Curtis Bay Association 9-12
9.2.4.11 Concerned Citizens for a Better Brooklyn 9-13
9.2.4.12 South Baltimore Business Alliance 9-13
9.2.4.13 National Aquarium at Baltimore 9-13
9.2.4.14 The Living Classrooms Foundation 9-13
9.2.4.15 Chesapeake Center for Youth Development 9-13
9.2.4.16 Maryland Environmental Trust (MET) 9-13
9.2.4.17 Baltimore Harbor Watershed Association 9-13
9.2.4.18 Maryland Historic Trust (MHT) 9-14

TABLE OF CONTENTS (continued)

Page

9.3 **PRELIMENARY DRAFT EIS AGENCY REVIEW** 9-14

10. **SUMMARY AND CONCLUSIONS** 10-1
10.1 PROPOSED MASONVILLE DMCF 10-1
10.2 NO ACTION ALTERNATIVE 10-8
10.3 CUMULATIVE IMPACTS 10-9

11. **DISTRIBUTION LIST** 11-1

12. **ORGANIZATIONAL CONFLICT OF INTEREST STATEMENT** 12-1

13. **REFERENCES** 13-1

LIST OF APPENDICES

APPENDIX A Water Quality and Sediment Quality

APPENDIX B Hydrology and Hydrodynamics Studies

APPENDIX C Ecological Studies

APPENDIX D Section 7 Consultation and EFH Assessment

APPENDIX E Upland Survey of Masonville Cove

APPENDIX F Alternatives Analysis

APPENDIX G Project Design

APPENDIX H Geotechnical Studies

APPENDIX I Section 404(b)(1) Evaluation

APPENDIX J Water Quality Modeling

APPENDIX K Emissions Calculations

APPENDIX L UMCES Impact Assessment

APPENDIX M Proposed Mitigation

APPENDIX N Project Construction

APPENDIX O Agency Coordination

APPENDIX P Public and DMMP Group Involvement

APPENDIX Q List of Preparers

LIST OF FIGURES

Number	Title	Page
1-1	Locations of Previously Considered, Current, and Potential DMCFs	1-3
1-2	Channels in the Baltimore Harbor	1-11
1-3	Location of the Proposed Masonville DMCF	1-20
2-1	Proposed Project Area, Proposed Masonville DMCF Footprint, and Adjacent Existing Land Area	2-2
2-2	Potential Method of Saltwater Intrusion in the Patuxent Formation	2-5
2-3	Thickness of the Arundel Formation in the Patapsco River	2-8
2-4	Elevations of the Patapsco Formation	2-9
2-5	Masonville Site Bathymetry	2-12
2-6	The Patapsco River and Its Tributaries	2-14
2-7	Water Levels per Return Period	2-17
2-8	Chesapeake Bay Physical Oceanographic Real-Time System Stations	2-18
2-9	Wind Rose at Tolchester Beach	2-19
2-10	Wind Direction Frequency Distribution at Tolchester Beach	2-19
2-11	Current Meter and Conductivity-Temperature-Depth (CTD) Profiler Deployment Locations in Patapsco River	2-24
2-12	Current Meter Deployment Locations Near Masonville	2-25
2-13a	Ebb Tide Surface Current Velocity	2-27
2-13b	Ebb Tide Bottom Current Velocity	2-27
2-14a	Flood Tide Surface Current Velocity	2-28
2-14b	Flood Tide Bottom Current Velocity	2-28
2-15	Location of CBP Water Quality Monitoring Station WT5.1 and Comprehensive Harbor Assessment and Regional Modeling Study (CHARMS) Stations 19 and 22	2-32
2-16	Nutrient Sample Locations	2-34
2-17	Sediment Sample Locations	2-37
2-18	Arsenic Concentrations in Surface Sediment Samples	2-44
2-19	Chromium Concentrations in Surface Sediment Samples	2-44
2-20	Copper Concentrations in Surface Sediment Samples	2-45
2-21	Lead Concentrations in Surface Sediment Samples	2-45
2-22	Mercury Concentrations in Surface Sediment Samples	2-46
2-23	Nickel Concentrations in Surface Sediment Samples	2-46
2-24	Zinc Concentrations in Surface Sediment Samples	2-47
2-25	Total PAH (ND=1/2DL) Concentrations in Surface Sediment Samples	2-47
2-26	Total PCB (ND=1/2DL) Concentrations in Surface Sediment Samples	2-48
2-27	Dioxin TEQ (ND=1/2DL) Concentrations in Surface Sediment Samples	2-48
2-28	Location of Sand Borrow Area Sample Locations	2-49
2-29	Plankton Trawl Locations for Masonville, Sollers Point, and Thoms Cove	2-56
2-30	Fisheries Sample Locations	2-59
2-31	Registered Pound Net Locations and Waterbody Reporting Area for Fishery Catch Data	2-63

2-32 Benthic Community Sample Locations 2-67
2-33 B-IBI Values for Each Sample Location 2-68
2-34 Areas of SAV Beds in Masonville Cove 2-72
2-35 Areas of Shallow Water Habitat in Proposed Masonville DMCF Footprint 2-74
2-36 Locations of Debris and Materials Observed During July 2005 Reconnaissance 2-86
2-37 100-Year Floodplain 2-90
2-38 Critical Area and the 100-ft Critical Area Buffer in the Vicinity of Masonville 2-92
2-39 Potential Cultural or Archeological Resource Targets Investigated for Eligibility for Listing on the National Register 2-99
2-40 Baltimore City Land Use 2-101
2-41 Points of Interest in the Vicinity of the Proposed Masonville DMCF 2-102
2-42 Baltimore City Census Tracts, Including Those in the Vicinity of the Proposed Masonville DMCF 2-103

3-1 Screening of the Dredged Material Placement Sites for Harbor Material 3-7
3-2 Committee Structure and Information Flow in the State of Maryland's DMMP 3-12
3-3 Existing Land Use in the Baltimore Harbor, 2001 3-19
3-4 Map of Existing Placement Locations 3-25
3-5 Screening of Masonville DMCF Alignments 3-42
3-6 Masonville Conceptual Alignments (CA) 3-44
3-7 Masonville Reconnaissance Alignment RA 3-45
3-8 Masonville Pre-Feasibility Alignments (PFA) 3-46
3-9 Masonville Final Feasibility Alignments (FFA) 3-48
3-10 Containment Structure Segments and Onsite Borrow Areas 3-50
3-11 Borrow Area Sections 3-51
3-12 Potential Study Alternatives 3-56
3-13 Alternatives Evaluated Under Each Scenario 3-56
3-14 Utilities Affected by the Proposed Project 3-58
3-15 Typical Dike Cross Sections 3-59
3-16 Typical Cofferdam and Rock Dike Cross-sections 3-62
3-17 Typical Onshore Dike Sections 3-64
3-18 Site Cost and Capacity Trends 3-68

4-1 Containment Structure Segments of the Recommended Plan (Alternative 3-C-10) 4-2
4-2 Boring Locations 4-6
4-3 Western Soil Profile 4-7
4-4 Northern Soil Profile 4-7
4-5 Eastern Soil Profile 4-8
4-6 Probe Locations 4-9
4-7 Topography of Soft Material/Firm Bottom Interface 4-10
4-8 Vane Shear Testing Locations 4-12
4-9 Typical Cofferdam Cross-Section 4-13
4-10 Typical Armored Sand Dike Cross-Section 4-14
4-11 Typical Beach Dike Cross-Section 4-15

4-12 Typical Onshore Dike Cross-Section 4-15
4-13 Typical Wet Basin Rock Dike Cross-Section 4-16
4-14 Borrow Area Plan View 4-18
4-15 Borrow Area Cross-Sections 4-19
4-16 Location of Stormwater Outfalls 4-22
4-17 Watermain Relocation Options 4-24
4-18 Onsite Relocation of Barges 4-26

5-1 Outcrop Elevations of the Patapsco Formation 5-9
5-2 With-Project Model Bathymetry 5-12
5-3 Observation Points Within Model 5-13
5-4a Water Surface Elevation Comparison, With and Without Project (1 of 2) 5-14
5-4b Water Surface Elevation Comparison, With and Without Project (2 of 2) 5-15
5-5 Ebb Tide Current Pattern (Surface) With and Without Project 5-17
5-6 Ebb Tide Current Pattern (Mid Depth) With and Without Project 5-18
5-7 Ebb Tide Current Pattern (Bottom) With and Without Project 5-19
5-8 Flood Tide Current Pattern (Surface) With and Without Project 5-120
5-9 Flood Tide Current Pattern (Mid Depth) With and Without Project 5-21
5-10 Flood Tide Current Pattern (Bottom) With and Without Project 5-22
5-11 Modeled Residence Time at Observation Points, With and Without Project 5-23
5-12 Sedimentation/Erosion Patterns, With Project (bottom) and Without Project (top) 5-25
5-13 Change in the Annual Sedimentation Rate Because of Proposed Masonville DMCF Project 5-26
5-14 Viewpoints Used in Aesthetic Analysis 5-74
5-15 Simulated View From Fort McHenry Before and After Project Construction 5-76
5-16 Total Middleground View from Fort McHenry Viewpoint 5-77
5-17 Portion of Middleground View Occupied by Proposed Masonville DMCF 5-78
5-18 Zones Used for Noise Analysis 5-81
5-19 Existing infrastructure near proposed Masonville DMCF 5-112

6-1 Masonville Cove Mitigation and Enhancement Projects 6-4
6-2 Tidal Wetland Creation and Enhancement Sites in Masonville Cove 6-5
6-3 Non-tidal Wetland Creation Site in Masonville Cove 6-6
6-4 Reef and Fish Habitat Creation in Masonville Cove 6-7
6-5 SWH Improvement Areas in Masonville Cove 6-8
6-6 Beach Creation in Masonville Cove 6-9
6-7 Landside Phase I Cleanup Area adjacent to Masonville Cove 6-10
6-8 Location of the Proposed Conservation Easement 6-11
6-9 Proposed Masonville Environmental Education and Nature Center with Hiking and Biking Trails 6-12
6-10 Proposed Locations for Eel Passages on the Patapsco River 6-14
6-11 Area Where Proposed Trash Interceptors may be Installed 6-15

LIST OF TABLES

Number	Title	Page
1-1	Planned Federal, State, Local, and Private Sector Dredging Needs in the Baltimore Harbor	1-7
1-2	MPA Harbor Dredged Material Placement Plan for HMI, Cox Creek, and Other Potential Placement Sites	1-14
2-1	Environmental Studies Completed During Each Survey Period	2-3
2-2	Soil Types at the Existing Masonville Site	2-6
2-3	Groundwater Contaminants Exceeding Groundwater Cleanup Standards	2-10
2-4	Astronomical Tidal Datum Characteristics for Baltimore, Ft. McHenry	2-15
2-5	Storm Inducted Water Levels	2-16
2-6	Design Wind Speeds per Direction and Return Period (mph)	2-20
2-7	Radically-Averaged Fetch Distance and Mean Water Depth Used for Wave Hindcasting	2-21
2-8	Offshore Significant Wave Heights (ft) – Masonville	2-22
2-9	Peak Spectral Wave Periods (sec) – Masonville	2-22
2-10	Measured Current Speeds (cm/sec) – Patapsco River	2-25
2-11	Average Seasonal Water Quality Data Measured at Masonville Sampling Locations	2-30
2-12	Average Seasonal Surface Water Quality Data Measured at CBP Monitoring Location WT5.1 (1995-2004)	2-31
2-13	Water Quality Data from Masonville Nutrient Sampling Locations in 2003 and 2004	2-35
2-14	Metal Concentrations in Surface Sediments	2-40
2-15	Concentrations of Organics and Dioxin TEQs for Surface Sediments within the Proposed DMCF Footprint and at Masonville Cove	2-41
2-16	Summary of Plankton Collected in the Masonville Study Area	2-57
2-17	Summary of Plankton Densities at the Sollers Point and Thoms Cove Control Sites	2-57
2-18	Summary Fisheries Data	2-61
2-19	Volume and Value of Commercial Fisheries in the Patapsco River	2-63
2-20	Total Volume and Value of Finfish Species Commercially Harvested in the Patapsco River, 1998-2003	2-63
2-21	Summary of Selected Masonville Benthic Data	2-69
2-22	Benthic Community Conditions for Corresponding B-IBI Values	2-70
2-23	Acres of SAV within the Project Alignment	2-72
2-24	Vegetation Observed During the Reconnaissance and State Feasibility-Level Surveys of Masonville from 2003 through 2005	2-78
2-25	RTE Plant Species of Baltimore City	2-79
2-26	Kurt Iron and Metal Derelict Vessel and Hazards Inventory	2-85
2-27	Materials Observed During the July 2005 Reconnaissance Visit	2-87

LIST OF TABLES (continued)

Number	Title	Page
2-28	Geographic and Population Characteristics for Neighboring Census Tracts, Baltimore City, and State of Maryland	2-105
2-29	Housing and Income Characteristics for Neighboring Census Tracts, Baltimore City, and State of Maryland	2-107
2-30	Employment by Sector in 2000	2-108
2-31	Business Characteristics for City of Baltimore and State of Maryland	2-109
2-32	Typical Noise Levels and Subjective Impressions	2-111
3-1	Timeline of Dredged Material Management in the State of Maryland	3-6
3-2	Selected Enhancement Sites from the 1982 BHEEP	3-9
3-3	Environmental Factors Considered in the State DMMP Screening Process	3-15
3-4	Placement Options Included in the State DMMP Screening Process	3-16
3-5	Projected Dredging Need and Capacity Shortfall through 2025	3-27
3-6	Types of Placement Facilities Evaluated in the Federal DMMP	3-28
3-7	Environmental Evaluation Parameters and Criteria	3-31
3-8	Comparison of Environmental Characteristics at Sparrows Point and BP-Fairfield	3-34
3-9	Advantages and Disadvantages of Scenarios A,B,C, and D	3-55
3-10	Summary of Site Characteristics	3-65
4-1	Preferred Alternative 3-C-10 Characteristics	4-3
4-2	Construction and Excavation Quantities	4-16
4-3	Project Costs	4-31
5-1	Water Surface Elevation Statistical Comparison, With and Without Project	5-15
5-2	Residence Time of Patapsco River, Upstream of Fort McHenry	5-22
5-3	Cross-Sectional Area of Tidal Average and Material Weighted Sediment Plumes at the Masonville Site for Dredging in the Borrow Area and Dredged Material Placement during Dike Construction	5-28
5-4a	Calculated Dissolved Concentrations for Clamshell Dredging of the Overburden (at a 6-cm/sec Average Tidal Velocity)	5-30
5-4b	Calculated Dissolved Concentrations for Placement of Material Dredged from the Borrow during Construction (at a 6-cm/sec Average Tidal Velocity)	5-30
5-4c	Calculated Dissolved Concentrations for Placement of Material Dredged from the Borrow during Construction (at a 6-cm/sec Average Tidal Velocity) Placement of Soft Clay during Dike Construction	5-31
5-5	Nutrient Parameters Measured in Site Water and Elutriates Prepared from Masonville Overburden Materials	5-32
5-6	Summary of Hart-Miller Island (HMI) Inflow Dredged Material Quality (1985-2005) Versus Quality of Sediments in Overburden of Masonville Borrow Area	5-35

5-7 Estimated Daily and Annual Loadings for the Masonville DMCF 5-39
5-8 Estimated Annual Loadings for the Masonville DMCF 5-39
5-9 Distance from Bald Eagle Nest Site BC-04-01 to Proposed Project Activities and Sites 5-56
5-10 Estimated Total Air Emissions from the Proposed Masonville DMCF Tasks .. 5-58
5-11 Summary of State Economic Impacts Associated with the Proposed Masonville DMCF 5-68
5-12 Summary of Local Economic Impacts Associated with the Proposed Masonville DMCF 5-69
5-13 Demographic Statistics for the Area near the Proposed Masonville DMCF 5-71
5-14 Changes to Middleground Views Associated with Proposed Harbor DMCF ... 5-75
5-15 Maximum Permissible Noise Levels for Different Types of Zoning 5-80
5-16 Summary of Noise Analysis 5-82
5-17 Summary of Habitat Types Affected By the Proposed Masonville DMCF 5-87
5-18 Summary of Impacts to Environmental Resources..... 5-88
5-19 Acreages of Current and Proposed In-Water Projects 5-93
5-20 Approximate Daily Loadings for Major Point Sources in the Patapsco-Back River Tributary System for 2003 5-99

8-1 Compliance Assessment 8-1
8-2 Permits and Coordination Required for the Proposed Masonville DMCF 8-4
8-3 Permits and Approvals: Additional Online Information..... 8-8

LIST OF ABBREVIATIONS, ACRONYMS, AND UNITS

3-D	Three Dimensional
404	Section 404 of the Clean Water Act
ADCP	Acoustic Doppler Current Profilers
AG	Air Gap
AM	Ante Meridiem, the Period between Midnight and Noon
AS	Atlantic Sturgeon
ATM	American Society for Testing Materials
avg	Average
AVS	Acid Volatile Sulfide
AWOIS	Automated Wreck and Obstruction Information System
BCBC	Brooklyn-Curtis Bay Coalition
BEWG	Bay Enhancement Working Group
BHEEP	Baltimore Harbor Environmental Enhancement Program
B-IBI	Benthic Index of Biotic Integrity
BOD	Biological Oxygen Demand
BP-Fairfield	British Petroleum-Amoco Asphalt Terminal in Fairfield
BWI	Baltimore-Washington International Airport
B&O	Baltimore and Ohio
°C	Degrees Celsius
C&D	Chesapeake and Delaware
CA	Conceptual Alignments
CAC	Citizens' Advisory Committee
CAMP	Critical Area Management Program
CBCAC	Chesapeake Bay Critical Area Commission
CBIA	Coastal Barrier Improvement Act
CBL	Chesapeake Biological Laboratory
CBP	Chesapeake Bay Program
CBRA	Coastal Barriers Resource Act
CDF	Confined Disposal Facility
CEM	Coastal Engineering Manual
CEQ	Council of Environmental Quality
CERCLA	Comprehensive Environmental Response Compensation and Liability Act
CFR	Code of Federal Regulations
CHARMS	Comprehensive Harbor Assessment and Regional Modeling Study
cm	Centimeter
cm/sec	Centimeters per Second
CO	Carbon Monoxide
COD	Chemical Oxygen Demand
COMAR	Code of Maryland Regulations
CO-OPS	Center for Operational Oceanographic Products and Services
CPT	Cone Penetration Tests

CTD	Conductivity-Temperature-Depth
CU	Current Meter
CWA	Clean Water Act
cy	Cubic Yard
CZMA	Coastal Zone Management Act
CZMP	Coastal Zone Management Program
DA	Department of the Army
dBA	A-Weighted Decibel
DDD	dichlorodiphenyldichloroethane
DDE	dichlorodiphenyldichloroethylene
DDT	dichlorodiphenyltrichloroethane
DEIS	Draft Environmental Impact Statement
DHPA	Designated Habitat Protection Area
DL	Detection Limit
DMCF	Dredged Material Containment Facility
DMMP	Dredged Material Management Program
DNPOP	Dredging Needs and Placement Options Program
DNR	Department of Natural Resources
DO	Dissolved Oxygen
E	East
EA	EA Engineering, Science, and Technology
EBA	EBA Engineering
ECR	Executive Committee Report
EFH	Essential Fish Habitat
e.g.	For Example (Exempli Gratia)
EIS	Environmental Impact Statement
EPA	Environmental Protection Agency
ER	Engineering Regulation
ERDC	Engineer Research and Development Center
ESA	Environmental Site Assessment
E2CR	Engineering Construction Consulting Remediation, Inc.
E2Si	Earth Engineering Science, Inc.
FEIS	Final Environmental Impact Statement
FFA	Final Feasibility Alignments
FHA	Federal Highway Administration
FI	Findling, Inc
FIS	Formerly Investigated Sites
FONSI	Finding of No Significant Impacts
FPPA	Farmland Protection Policy Act
FTE	Full Time Equivalent
ft	foot or feet
ft/s	Feet per second

g	gram
GBA	Gahagan & Bryant Associates, Inc.
GIS	Geographic Information Systems
H_s	Significant Wave Height
HAPC	Habitat Areas of Particular Concern
HMI	Hart-Miller Island
HPL	Horn Point Laboratory
HP	Horsepower
HTRW	Hazardous, Toxic and Radioactive Waste
IDA	Intensely Developed Area
i.e.	That is (id est)
IMPLAN	Impact Planning
ISG	International Steel Group
ITM	Inland Testing Manual
JE	Joint Evaluation Committee
JV	Joint Venture
kg	Kilogram
KIM	Kurt Iron and Metal Site.
lb	Pound
LBP	Lead Based Paint
m	Meters
M&N	Moffatt and Nichol Engineers
MAFMC	Mid-Atlantic Fisheries Management Council
MBSS	Maryland Biological Stream Survey
mcy	Million Cubic Yards
MCAC	Maryland Critical Areas Commission
MD	Maryland
MDE	Maryland Department of the Environment
MDOT	Maryland Department of Transportation
MEC	Munitions of Explosive Concern
MES	Maryland Environmental Service
MET	Meteorological Sensors
mg	milligram
MGS	Maryland Geological Survey
mg C/L	Milligrams of Carbon per Liter
mg/kg	Milligrams per Kilogram
mg/L	Milligrams per Liter
mg N/L	Milligrams of Nitrogen per Liter
mg P/L	Milligrams of Phosphorus per Liter
MHT	Maryland Historical Trust

MHW	Mean High Water
MLW	Mean Low Water
MLLW	Mean Lower Low Water
MMT	Masonville Marine Terminal
MPA	Maryland Port Administration
mph	Miles per Hour
m/s	Meters per second
MSDC	Maryland Shipbuilding and Dry-dock Company
MSFCMA	Magnuson-Stevens Fishery Conservation and Management Act
N	North
NA	Not Applicable
NAAQS	National Ambient Air Quality Standards
NAVD	North American Vertical Datum
nc.	
NCCTWG	North Cell Closure Team Working Group
NCDC	National Climatic Data Center
ND	Non-Detection
NE	Northeast
NEPA	National Environmental Policy Act
NFRAP	No Further Remedial Action Planned
NGVD	National Geodetic Vertical Datum
NHPA	National Historic Preservation Act
NMFS	National Marine Fisheries Service
NNE	North-Northeast
No.	Number
NO_x	Nitrogen Oxides
NOAA	National Oceanic and Atmospheric Administration
NOBs	Natural Oyster Bars
NOI	Notice of Intent
NOS	National Ocean Service
NPL	National Priority List
NRCS	Natural Resources Conservation Service
NTU	Nephelometric Turbidity Unit
NW	Northwest
OTC	Ozone Transport Commission
OTR	Ozone Transport Region
OSHA	Occupational Safety and Health Administration
PAH	Polynuclear Aromatic Hydrocarbon
PCBs	Polychlorinated Biphenyls
PEL	Probable Effect Level
PFA	Pre-Feasibility Alignments
pg	Picogram
PIERP	Poplar Island Environmental Restoration Project

PM	Post Meridiem, the Period between Noon and Midnight
PM_{10}	Particulate Matter up to 10 micrograms
PORTS	Physical Oceanographic Real-Time System
ppt	Parts per Thousand
RA	Reconnaissance Alignment
RAP	Response Action Plan
RCA	Resource Conservation Area
RCRA	Resource Conservation and Recovery Act
RCG&A	R. Christopher Goodwin & Associates
RMS	Root Mean Squared
ROD	Record of Decision
RO-RO	Roll On-Roll Off
RPC	Regional Planning Commission
RTE	Rare, Threatened, and Endangered
S	South
SAIC	Science Applications International Corporation
SAV	Submerged Aquatic Vegetation
SE	Southeast
SEM	Simultaneously Extracted Metals
SFY	State Fiscal Year
SHPO	State Historic Preservation Office
SNS	Shortnose Sturgeon
sp.	Species
SPDES	State Pollution Discharge Elimination System
SQGs	Sediment Quality Guidelines
SVOC	Semi-Volatile Organic Compounds
SW	Southwest
SWAP	Surface Water Appropriations Permit
SWH	Shallow Water Habitat
S1	Highly State Rare
TEL	Threshold Effect Level
TEQ	Threshold Equivalency Quotient
TIN	Triangulated Irregular Network
TKN	Total Kjeldahl Nitrogen
TMDL	Total Maximum Daily Load
TOC	Total Organic Carbon
TOY	Time of Year
T_p	Peak Spectral Wave Period
TPH	Total Petroleum Hydrocarbons
tpy	Tons per Year
TSS	Total Suspended Solids
µg	Microgram

UMCES	University of Maryland Center for Environmental Science
U.S.	United States
USACE	United States Army Corps of Engineers
USC	United States Code
USDA	United States Department of Agriculture
USEPA	United States Environmental Protection Agency
USFWS	United States Fish and Wildlife Service
USGS	United States Geological Survey
UXO	Unexploded Ordnance
VCP	Voluntary Clean Program
VOCs	Volatile Organic Compounds
VIMS	Virginia Institute of Marine Science
VRAP	Visual Resources Assessment Procedure
W	West
WL	Water Levels (Tide Gauge)
WQC	Water Quality Certification
WWTP	Wastewater Treatment Plant
YOY	Young of the Year