

**Building 271 – Turkey Mating and Breeding House
USDA – Beltsville Agricultural Research Center (BARC)
Bureau of Engraving and Printing EIS
Beltsville, Prince George’s County, Maryland
Ca. 1936**

Building 271 was constructed ca. 1936 and functioned as a turkey mating and breeding house on the Central Farm within the U.S. Department of Agriculture’s (USDA) Agricultural Research Service’s Beltsville Agricultural Research Center (BARC). It was built in an area used by the Bureau of Animal Industry (BAI). Building 271 has a rectangular plan and faces north towards an unnamed access road on northside that is perpendicular to Poultry Road to its east. The single-story building is oriented on an east-west axis. It is wood-frame construction and rests on a concrete foundation. The exterior walls are clad in wood clapboard siding. The primary (north) façade has two equally-spaced metal vents extending from the wall. Views of the south (rear) façade are obscured by vegetation but there appear to be four projecting box-like frames around window openings. The east elevation contains a single off-center wood door, while the west elevation has no openings. The east and west elevations each have a triangular vent in the apex of the gable. The side-gable metal roof has a non-historic elastomeric roof coating. The interior of Building 271 is a single open space, with an alley on the south side and wood-frame pens with chicken wire on the north side. The interior walls are clad with broad rectangular boards.

Building 271 is located on BARC’s 2,980-acre Central Farm, the largest and oldest of all of BARC’s farms. The USDA acquired the Central Farm in stages between 1910 and 1939; most of the buildings and landscape of the Central Farm were developed between 1911 and 1944. During the 1920s, the BAI’s Animal Husbandry Division led the continued development of the site and was the largest section (i.e., in terms of both areas occupied and staff) at BARC. The division’s research initially focused on the breeding of all domestic animals, except dairy (Robinson and Associates 1998). The BAI transferred other divisions to BARC during the late 1920s and early 1930s using New Deal funding sources at the Central and East Farms; the Swine Research unit was relocated from the Central Farm to the East Farm during the period between 1938 and 1942 (Robinson and Associates 1998). Over the years, the BAI’s Animal Husbandry Division undertook critical poultry and swine research that improved the size and health of the farm animals; the BAI’s researchers conducted important research at BARC that led to major improvements in eradicating and treating contagious diseases in farm animals, reducing parasite infestations, and improving nutrition.

In 1997, BARC was determined eligible for individual listing in the National Register for Historic Places (NRHP) as the largest national research facility for the USDA and for its role as the most diversified agricultural research complex in the world. The evaluation finds that while Building 271 is not individually significant, it contributes to the overall significance of BARC. Building 271 is a contributing property within BARC under Criterion A at the national level for its historical association with agricultural experimentation and under Criterion C as it embodies the distinctive characteristics of experimental agricultural architecture.

**MARYLAND HISTORICAL TRUST
DETERMINATION OF ELIGIBILITY FORM**

NR Eligible: yes
no

Property Name: Building 271: Turkey Mating and Breeding House Inventory Number: PG:62-71
 Address: 10300 Baltimore Avenue Building 271, Central Farm, Beltsville Historic district: yes no
Agricultural Research Center
 City: Beltsville Zip Code: 20705 County: Prince Georges
 USGS Quadrangle(s): Beltsville
 Property Owner: U.S.A. - U.S. Department of Agriculture (USDA) Tax Account ID Number: 01-0070151
 Tax Map Parcel Number(s): 0143 Tax Map Number: 0019
 Project: Bureau of Engraving and Printing EIS Agency: USACE-Baltimore District
 Agency Prepared By: AECOM
 Preparer's Name: Melanie Lytle, MA Date Prepared: 10/31/2019
 Documentation is presented in: MIHP Form, PG:62-14
 Preparer's Eligibility Recommendation: Eligibility recommended Eligibility not recommended
 Criteria: A B C D Considerations: A B C D E F G
Complete if the property is a contributing or non-contributing resource to a NR district/property:
 Name of the District/Property: Beltsville Agricultural Research Center
 Inventory Number: PG:62-14 Eligible: yes Listed: yes
 Site visit by MHT Staff yes no Name: _____ Date: _____

Description of Property and Justification: *(Please attach map and photo)*

The U.S. Department of Agriculture's (USDA) Agricultural Research Service's (ARS) Beltsville Agricultural Research Center (BARC) was one of the largest agricultural research facilities in the United States (Figures 1 and 2). Owned by the USDA, the facility was established in Beltsville in 1910 and significantly expanded in the 1930s and 1940s. In the 1960s, the USDA's research program began evolving from an internationally recognized research center to a decentralized model. In 1984, BARC was re-designated as a regional center. BARC's period of significance ranges from its inception in 1910 to its reclassification as a regional center in 1984.

BUILDING LOCATION

BARC identifies the address of Building 271 as 10300 Baltimore Avenue, Building 271, Central Farm. Building 271 is located 775' west of Poultry Road; 920' southwest of the intersection of Odell and Poultry Roads.

MARYLAND HISTORICAL TRUST REVIEW	
Eligibility recommended <input type="checkbox"/>	Eligibility not recommended <input type="checkbox"/>
Criteria: <input type="checkbox"/> A <input type="checkbox"/> B <input type="checkbox"/> C <input type="checkbox"/> D	Considerations: <input type="checkbox"/> A <input type="checkbox"/> B <input type="checkbox"/> C <input type="checkbox"/> D <input type="checkbox"/> E <input type="checkbox"/> F <input type="checkbox"/> G
MHT Comments:	
_____ Reviewer, Office of Preservation Services	_____ Date
_____ Reviewer, National Register Program	_____ Date

BUILDING DESCRIPTION

Located in the USDA ARS BARC’s Central Farm (Figures 3 through 6), Building 271 (Photos 1 through 4) was built as a Turkey Mating and Breeding House, ca. 1936 (Robinson and Associates 1998). Building 271 has a rectangular plan and faces north towards an unnamed access road on northside that is perpendicular to Poultry Road to its east. The single-story building is oriented on an east-west axis. It is built with wood-frame construction and rests on a concrete foundation. The exterior walls are clad in wood clapboard siding. The primary (north) façade has two equally-spaced metal vents from the wall (Photo 1). Views of the south (rear) façade are obscured by vegetation but there appear to be four projecting box-like frames around window openings. The east elevation contains a single off-center wood door (Photo 2), while the west elevation has no openings (Photo 3). The east and west elevations each have a triangular vent in the apex of the gable. The side-gable metal roof has a non-historic elastomeric roof coating (Photo 3). The interior of Building 271 is a single open space, with an alley on the south side and wood-frame pens with chicken wire on the north side (Photo 4). The interior walls are clad with broad rectangular boards.

Building 271, which is currently vacant, is in good condition.

HISTORY OF PROPERTY

Central Farm

Building 271, constructed in ca. 1936, is located on the 2,980-acre Central Farm. The largest and oldest of all of BARC’s farms, the USDA acquired the Central Farm in stages between 1910 and 1939; most of the buildings and landscape of the Central Farm were developed between 1911 and 1944. The Central Farm is located at the center of BARC and is adjacent to BARC’s Linkage Farm to the west, single-family homes along Odell Road to the north, facilities associated with the U.S. Department of Health and Human Services (DHHS) and U.S. Department of State (DOS) to the northeast, the Baltimore-Washington Parkway to the east, and the City of Greenbelt to the south. The Central Farm has approximately 12 clusters of buildings situated on approximately 336 acres (of the 2,980-acre total), as well as pastures, wetlands, and forested areas used for animal husbandry, production crops, animal and plant research, and wildlife management. The USDA’s Bureau of Animal Industry (BAI) has historically been the Central Farm’s main user (Robinson and Associates 1998).

The USDA acquired the first portion of the Central Farm in 1910 when it purchased 475 acres of the Hall Farm for the Farm Dairy and Animal Husbandry Divisions of the BAI to establish an experimental farm. To accommodate the experimental farm’s many research tasks during BARC’s early period (i.e., 1910-1933), the USDA constructed laboratories, farm buildings, pastures, and staff housing. In addition, the BAI added laboratories for its Pathology and Zoological Divisions.

In the 1920s, the Bureau of Plant Industry (BPI) began to operate at BARC on approximately 425 acres of leased land that was subsequently purchased with Public Works Administration (PWA) funds in the 1930s, expanding the Central Farm (Wiser and Rasmussen 1966; USDA ca. 1937). In 1924, the Farm Dairy and Animal Husbandry Divisions separated into the Bureau of Dairy Industry (BDI) and the BAI. The BDI used 190 acres for continued experiments on dairy cattle breeding, forage crop, silage, and milk research, and the BAI kept 285 acres for its animal research. By 1925, the USDA owned 1,062 acres of the Central Farm and leased about 1,000 more acres (Wiser and Rasmussen 1966). By 1933, four land purchases totaling an additional 1,381 acres further increased the Central Farm’s size (USDA ca. 1937; Robinson and Associates 1998).

The majority of the Central Farm was acquired under New Deal policies and funding of the 1930s, when the USDA transformed BARC into a model experiment station. A series of land acquisitions during the 1930s grew BARC to more than 12,000 acres. With this expansion, many of the Bureaus either established, enlarged, or constructed new research facilities on the Central Farm.

MARYLAND HISTORICAL TRUST REVIEW													
Eligibility recommended _____					Eligibility not recommended _____								
Criteria:	___ A	___ B	___ C	___ D	Considerations:	___ A	___ B	___ C	___ D	___ E	___ F	___ G	
MHT Comments:													
_____							_____						
Reviewer, Office of Preservation Services							Date						
_____							_____						
Reviewer, National Register Program							Date						

These included the BAI’s pathology, zoology, and insecticide divisions, the Bureau of Entomology and Plant Quarantine, the Bureau of Human Nutrition and Home Economics, the Bureau of Agricultural Engineering, the Bureau of Cultural and Industrial Chemistry, and the Food and Drug Administration (Robinson and Associates 1998).

The expansion of BARC required major infrastructure improvements that were undertaken with PWA funding and oversight, and Civilian Conservation Corps (CCC) assistance and labor. A CCC camp was established on the north end of the Central Farm in 1933; eventually, four CCC camps were established at BARC, although their exact locations are not known. The CCC workers cleared and drained land, built fences and roads, and constructed small sheds and structures. The overall design of the Central Farm in the 1930s was guided by a master plan that was the work of A.D. Taylor and Delos Smith; H.F. Seahorn of the Public Buildings Administration; Robert T. Walker, CCC landscape architect; and Hugh H. Bennet of the Soil Conservation Service (Robinson and Associates 1998). The Central Farm’s character-defining landscape features include:

- Topographical and anthropogenically altered features, such as major paved roads, minor service and field roads, drainage systems, Beaver Dam Creek, and graded fields;
- Vegetation features, such as field and research crops, pastures, Beltsville Seasonal Ponds, Beltsville Bottomland Forest, and meadows;
- Circulation features, such as Dairy Farm, Powder Mill, Entomology, Research, BioControl, Poultry, and Beaver Dam Roads, as well as secondary and service roads;
- Five main clusters of development, including the 100 Area Cluster (BDI), 200 Area Cluster (BAI – Poultry Research Division), 300 Area Cluster (BAI – Parasitological Laboratory of the Zoological Division), 400 Area Cluster (Bureau of Entomology and Plant Quarantine [BEPQ] – Entomology Research Division), and 1000 Area Cluster (Animal Disease Station); and
- Small-scale features, such as fencing, culverts, an amphitheater, and a cemetery (Robinson and Associates 1998).

Bureau of Animal Industry

The USDA’s BAI, the earliest of the USDA’s research bureaus at BARC, came to the Central Farm in 1910 when its Dairy and Animal Husbandry Divisions established an experimental farm within BARC’s initial 475 acres. When the USDA reorganized the Dairy Division into a separate BDI, the BAI retained 285 acres of the Central Farm for its Animal Husbandry Division. During the 1920s, the BAI’s Animal Husbandry Division led the continued development of the site and was the largest section (i.e., in terms of both areas occupied and staff) at BARC. The division’s research initially focused on the breeding of all domestic animals, except dairy (Robinson and Associates 1998).

By the early 1930s, the BAI’s Animal Husbandry Division’s needs far exceeded its facilities. To address these needs, the PWA allotted over \$1 million for a major construction program at BARC that included laboratories, an abattoir (slaughterhouse), and animal buildings. These facilities were constructed at BARC with the assistance of CCC workers, with funding and oversight provided by the PWA and the Civil Works Administration. A new Main Laboratory (i.e., Building 200), constructed under this program, was the showpiece of the new animal husbandry area.

As a result of the expansion, by the mid-1930s, the BAI’s Animal Husbandry Division was the largest experimental farm in the country and the center of nation’s research on animal husbandry (Robinson and Associates 1998). In addition to animal husbandry, the BAI transferred other divisions to BARC during the late 1920s and early 1930s using New Deal funding sources at the Central and East Farms. The BAI’s Zoological Division moved its experimental headquarters to, and the BAI’s Animal Disease Station was established at BARC’s Central Farm in 1929 and expanded in 1935 (Robinson and Associates 1998).

In 1953, the USDA undertook a major reorganization and decentralization of the USDA’s agricultural research program that

MARYLAND HISTORICAL TRUST REVIEW													
Eligibility recommended				Eligibility not recommended									
Criteria:	___ A	___ B	___ C	___ D	Considerations:	___ A	___ B	___ C	___ D	___ E	___ F	___ G	
MHT Comments:													
_____							_____						
Reviewer, Office of Preservation Services							Date						
_____							_____						
Reviewer, National Register Program							Date						

continued through the 1970s (Office of Technology Assessment [OTA] 1981). The decentralization had long-lasting consequences for BARC. The department’s scientific bureaus, including the BAI, were discontinued and the department’s research functions were centralized under the new Agricultural Research Administration (now the ARS) (OTA 1981). The USDA again reorganized in 1972 with administrative decentralization as its goal (OTA 1981). Through this process, operating responsibility was delegated to four regions, which were then subdivided into research area centers. BARC’s scientists and facilities thus became a regional research facility, rather than a national one (OTA 1981). By 1980, the USDA’s research program was highly decentralized, with research undertaken at 148 locations, including the much diminished 450-scientist facility at BARC (OTA 1981).

Over the years, the BAI’s researchers conducted important research at BARC that has led to major improvements in eradicating and treating contagious diseases in farm animals, reducing parasite infestations, and improving nutrition. The BAI’s Animal Husbandry Division undertook critical poultry and swine research that improved the size and health of the farm animals. The BAI’s Zoology Division’s parasite research brought innovative new approaches to treating infestations. The BAI’s Animal Disease Station developed vaccines to prevent Bang’s disease and developed sterilization methods for contaminated hides (Robinson and Associates 1998).

History of the Turkey Mating and Breeding House, Building 271

Building 271 is one of three identical turkey mating and breeding houses (Buildings 269-271) that were built ca. 1936 (Building 269 is no longer extant) (Robinson and Associates 1998). The timeline and construction methodology for Building 271 is consistent with the New Deal development of BARC, which prioritized simple utilitarian design elements (Robinson and Associates 1998).

According to John R. Mohler’s publication Federal Poultry Research at the Agricultural Research Center, Beltsville, MD from 1939, the poultry farm had been used for experimental work for more than 25 years by the late 1930s. In 1934, around the time when new laboratory buildings were being constructed, the farm was enlarged, and the poultry houses rebuilt. Thus, at the time of Mohler’s report, all the poultry houses and other buildings used for poultry investigations, including Building 271, were practically new, with only one original building still standing (Mohler 1939).

Mohler describes the poultry farm as consisting of four laboratory buildings, a central heating plant, and more than 200 houses of various sizes for housing the experimental flocks and equipment. At this time, the poultry buildings had the capacity to house approximately 7,000 adult chickens, 1,500 turkeys, and 200 pigeons. Additionally, facilities for brooding 13,000 chicks and 2,500 poults during the normal brooding period (February 1-June 1) were available, with incubator capacity of about 150,000 eggs (Mohler 1939). The building appears to have been used as a turkey mating and breeding house since its construction.

NATIONAL REGISTER OF HISTORIC PLACES EVALUATION

Building 271 was surveyed in 1997 (Robinson and Associates 1998) but not evaluated to determine the building’s individual significance or status as a contributing or non-contributing property at BARC, a 6,582-acre federal agricultural research facility. BARC was determined eligible in its entirety for listing in the National Register of Historic Places (NRHP) as the largest national research facility for the USDA and for its role as the most diversified agricultural research complex in the world. This evaluation finds that while Building 271 is not individually significant, it contributes to the overall significance of BARC. The history and development of the agricultural research facility also reflects New Deal policies and programs, and contains notable landscape architecture, Georgian Revival architecture, and experimental agricultural architecture. The criteria applied to evaluate properties for the NRHP are presented below.

MARYLAND HISTORICAL TRUST REVIEW													
Eligibility recommended				Eligibility not recommended									
Criteria:	<u> </u> A	<u> </u> B	<u> </u> C	<u> </u> D	Considerations:	<u> </u> A	<u> </u> B	<u> </u> C	<u> </u> D	<u> </u> E	<u> </u> F	<u> </u> G	
MHT Comments:													
_____							_____						
Reviewer, Office of Preservation Services							Date						
_____							_____						
Reviewer, National Register Program							Date						

Under Criterion A, Building 271 is a contributing property within BARC, which is significant at the national level for its association with events that have made significant contributions to the broad pattern of our history with agricultural experimentation. Many aspects of twentieth century living for the farmer and consumer were influenced by the scientific research conducted at BARC. BARC is a prominent example of the federal role in agricultural research, scientific agricultural research in general, and New Deal policies and programs, such as the 1930s agricultural policies and funding, the PWA, and the CCC, which all played important roles in shaping the experimental farm. BARC's scientists and researchers have made major contributions toward scientific knowledge that have resulted in incredible advances in crop production, plant and animal disease control, and pest control. Building 271 was specifically designed and operated as a Turkey Mating and Breeding House within the BAI's 200 Area Cluster - Poultry Research Division. BARC scientists and researchers made valuable scientific contributions, both in foundational and applicable science.

BARC and Building 271 have not been determined significant under Criterion B for its association with the lives of persons significant in our past.

Under Criterion C, Building 271 is a contributing property within BARC, as it embodies the distinctive characteristics of a type, period, or method of construction. The physical appearance of BARC was strongly influenced in the 1930s by the planning team of A.D. Taylor, landscape architect, and Delos Smith, architect. The majority of BARC's buildings share a Georgian Revival style and/or display the characteristics of experimental agricultural architecture. BARC's landscape includes major paved roads, minor service roads, field and research crops, pasture lands, seasonal ponds, forests, sustainable meadows, and other landscape features and buildings. Building 271, while relatively modest in design, represents an example of the experimental and purpose-driven agricultural architecture trends for which BARC is significant, and contributes to the overall landscape.

Neither BARC nor Building 271 specifically has been evaluated under Criterion D for its yielding, or likelihood to yield, information important in prehistory or history.

Building 271 retains its original location and setting within an agricultural research complex. Building 271 is specifically linked in its design and operation as a Turkey Mating and Breeding House and its ties to the BAI's 200 Area Cluster (Poultry Research Division) research buildings. The feeling of, and association with, an agricultural research center is intact. Building 271 maintains key elements of its original design including massing, fenestration, roofing pattern, cladding, and internal layouts. Building 271 retains its integrity of design, workmanship, and materials. It is in good condition.

Although Building 271 does not reach the level of significance necessary for individual listing on the NRHP, it maintains its significance within BARC under Criteria A and C.

REFERENCES

Mohler, John R. 1939 Federal Poultry Research at the Agricultural Research Center, Beltsville, MD. United States Department of Agriculture Miscellaneous Publication No. 368. Pages 1-7. <https://play.google.com/books/reader?id=s3iVjVr3IKYC&printsec=frontcover&pg=GBS.PP1> (accessed October 10, 2019).

Office of Technology Assessment (OTA), U.S. Food and Agricultural Research Advisory Panel 1981 An Assessment of the United States Food and Agricultural Research System. <https://books.google.com/books?id=0Muy9v0PQckC&lpg=PA29&dq=The%20Role%20and%20Development%20of%20Public%20Agricultural%20Research&pg=PA29#v=onepage&q&f=false> (accessed October 10, 2019).

MARYLAND HISTORICAL TRUST REVIEW													
Eligibility recommended					Eligibility not recommended								
Criteria:	<u> </u> A	<u> </u> B	<u> </u> C	<u> </u> D	Considerations:	<u> </u> A	<u> </u> B	<u> </u> C	<u> </u> D	<u> </u> E	<u> </u> F	<u> </u> G	
MHT Comments:													
_____							_____						
Reviewer, Office of Preservation Services							Date						
_____							_____						
Reviewer, National Register Program							Date						

Robinson and Associates

1998 Historic Site Survey, Beltsville Agricultural Research Center, Beltsville, Maryland. On file at the Maryland Historical Trust.

United States Department of Agriculture

ca. 1937 The National Agricultural Research Center of the Department of Agriculture. USDA Library, Special Collections 360.

Wiser, Vivian and Wayne D. Rasmussen

1966 "Background for Plenty: A National Center for Agricultural Research." Maryland Historical Magazine 61:4, December 1966.

MARYLAND HISTORICAL TRUST REVIEW

Eligibility recommended _____

Eligibility not recommended _____

Criteria: ___ A ___ B ___ C ___ D Considerations: ___ A ___ B ___ C ___ D ___ E ___ F ___ G








MHT Comments:



Reviewer, Office of Preservation Services

Date

Reviewer, National Register Program

Date

-  Survey Boundary
-  BARC Boundary
-  Central Farm
-  East Farm
-  Linkage Farm
-  North Farm
-  South Farm










CLIENT	USACE - Baltimore District
PROJ	Bureau of Engraving and Printing EIS
SCALE	1:85,000
SOURCE	USGS 7.5' Beltsville, MD Quad, 1979


\\URSgermantown.us.ie.urs\germantown\Projects\ENVIAP\CRM\USDA - BARC CRM study, Phase 1\900-GIS and Graphics\920 GIS\ArchHist\Fig1B264



TITLE	Beltsville Agricultural Research Center Overview Map Building 271 – Turkey Mating and Breeding House (PG:62-71)
-------	---

PROJ NO	
FIGURE	1

-  Survey Boundary
-  BARC Boundary
-  Central Farm
-  East Farm
-  Linkage Farm
-  North Farm
-  South Farm



0 1 2 3 Miles

CLIENT USACE - Baltimore District
 PROJ Bureau of Engraving and Printing EIS
 SCALE 1:85,000
 SOURCE ESRI 2019





\\URSGermantown.us.ie.urs\Germantown\Projects\ENVI\AP\CRM\USDA - BARC CRM study, Phase 1\900-GIS and Graphics\920 GIS\ArchHist\Fig1B264





TITLE Beltsville Agricultural Research Center Overview Map
 Building 271 - Turkey Mating and Breeding House
 (PG:62-71)


PROJ NO

FIGURE

-  Survey Boundary
-  BARC Boundary
-  Central Farm
-  Surveyed Building/Structure



CLIENT	USACE - Baltimore District
PROJ	Bureau of Engraving and Printing EIS
SCALE	1:31,000
SOURCE	ESRI 2019





TITLE	Beltsville Agricultural Research Center Central Farm Building 271 – Turkey Mating and Breeding House (PG:62-71)
-------	---

PROJ NO	
FIGURE	

\\URSGermantown.us.ie.urs\Germantown\Projects\ENVI\AP\CRM\USDA - BARC CRM study, Phase 1\900-GIS and Graphics\920 GIS\ArchHist\Fig1B264



Survey Boundary
 BARC Boundary





CLIENT	USACE - Baltimore District
PROJ	Bureau of Engraving and Printing EIS
SCALE	1:24,000
SOURCE	USGS 7.5' Beltsville, MD Quad, 1979
\\URSGermantown.us.ie.urs\Germantown\Projects\ENVIAP\CRM\USDA - BARC CRM study, Phase 1\900-GIS and Graphics\920 GIS\ArchHist\Fig4_271	



TITLE Beltsville Agricultural Research Center Building 271 – Turkey Mating and Breeding House (PG:62-71)	
PROJ NO	
FIGURE	
	4

 Survey Boundary
 BARC Boundary



CLIENT	USACE - Baltimore District
PROJ	Bureau of Engraving and Printing EIS
SCALE	1:6,000
SOURCE	USGS 7.5' Beltsville, MD Quad, 1979



\\URSGermantown.us.ie.urs\Germantown\Projects\ENV\IAP\CRM\USDA - BARC CRM study, Phase 1\900-GIS and Graphics\920 GIS\ArchHist\Fig5_271




TITLE	Beltsville Agricultural Research Center Building 271 – Turkey Mating and Breeding House (PG:62-71)
-------	--

PROJ NO	
---------	--

FIGURE	5
--------	---

 Survey Boundary
 BARC Boundary



0 0.095 0.19 0.285 Miles

CLIENT USACE - Baltimore District
 PROJ Bureau of Engraving and Printing EIS
 SCALE 1:6,000
 SOURCE ESRI 2019

\\URSGermantown.us.ie.urs\Germantown\Projects\ENV\IAP\CRM\USDA - BARC CRM study, Phase 1\900-GIS and Graphics\920 GIS\ArchHist\Fig1B264



TITLE Beltsville Agricultural Research Center
 Building 271 – Turkey Mating and Breeding House
 (PG:62-71)

PROJ NO

FIGURE

Building 271: Turkey Mating and Breeding House
USDA – Beltsville Agricultural Research Center (BARC)
Bureau of Engraving and Printing EIS
10300 Baltimore Avenue, Central Farm
Prince George’s County, MD
Photographer: Rebecca McGovern, Architectural Historian
September 25, 2019
MD SHPO

Archival Black and White Photographs and Digital Photographs for the Maryland Historical Trust.

1. PG:62-71_2019_09_25_01.tif, Building 271, Turkey Mating and Breeding House, Central Farm, View of North and West Elevations, Looking Southeast
2. PG:62-71_2019_09_25_02.tif, Building 271, Turkey Mating and Breeding House, Central Farm, View of East and North Elevations, Looking Southwest
3. PG:62-71_2019_09_25_03.tif, Building 271, Turkey Mating and Breeding House, Central Farm, View of South and East Elevations, Looking Northwest
4. PG:62-71_2019_09_25_04.tif, Building 271, Turkey Mating and Breeding House, Central Farm, Overview of the Interior, Looking East



Photo 1 – Building 271, Turkey Mating and Breeding House, Central Farm, View of North and West Elevations, Looking Southeast



Photo 2 – Building 271, Turkey Mating and Breeding House, Central Farm, View of East and North Elevations, Looking Southwest

CLIENT	USACE - Baltimore District	TITLE	Photographs
PROJ	Bureau of Engraving and Printing EIS		Building 271 – Turkey Mating and Breeding House
SCALE	-		(PG:62-71)
SOURCE	AECOM		
\\URSGermantown.us.ie.urs\Germantown\Projects\ENV\IAP\CRM\USDA - BARC CRM study, Phase 1\900-GIS and Graphics\920 GIS\ArchHist\271\Fig_Photo2711.mxd			PROJ NO
			FIGURE



Photo 3 – Building 271, Turkey Mating and Breeding House, Central Farm, View of South and East Elevations, Looking Northwest



Photo 4 – Building 271, Turkey Mating and Breeding House, Central Farm, Overview of the Interior, Looking East

CLIENT	USACE - Baltimore District	TITLE	Photographs Building 271 – Turkey Mating and Breeding House (PG:62-71)
PROJ	Bureau of Engraving and Printing EIS		
SCALE	-		
SOURCE	AECOM		
\\URSGermantown.us.ie.urs\Germantown\Projects\ENVI\AP\CRM\USDA - BARC CRM study, Phase 1\900-GIS and Graphics\920 GIS\ArchHist\271\Fig_Photo2712.mxd			PROJ NO
			FIGURE